# **SPECIFICATION**

for the construction of

# Mount Beauty & District Men's Shed Extension

at

Tennis Court Avenue, Mount Beauty

October 2019

**Issue A** 



P.O. Box 382 Mt Beauty Victoria 3699 Ph. 0419 399737 info@mountaincreekarch.com

#### 1. **DEMOLITION**

Remove window to existing toilets. Make good. Remove downpipe where shown on drawings.

#### 2. EXCAVATION AND FILL

Excavation and foundation preparation has been done.

Excavate for raft slab and edge beams to engineer's design.

Termite control: Provide 150mm visual barrier to perimeter of concrete slab. Refer Concrete section for additional termite treatment.

#### 3. STORM DRAINAGE

Install downpipes where shown on drawings to match existing. Stormwater connection by others

#### 4. CONCRETE

Supply and install termite control, concrete, reinforcing steel, formwork, for strip footings, floor slabs, paving, pits, curbs etc.

Concrete to be built in accordance with AS2870 Residential Slabs & Footings.

Construct concrete raft slab, edge beams and internal beams as per engineering drawings.

| Item                    | Description  |
|-------------------------|--|
| Reinforcing steel:      | Clean, no mud, oil or rust. Provide bar chairs                     |
| Waterproofing membrane: | 0.2mm thick plastic premium quality                                |
| Concrete                | 20mPa strength at 28 days.   |
|                         | Use no additives without authority                                 |
| Termite control         | Provide Termimesh stainless steel mesh or Kordon sheet to all slab |
|                         | penetrations.  |

#### 5. METAL FRAMING

Supply and install steel portal frames, wall frames, roof framing, verandah columns to engineer's specifications.

#### 6. CARPENTRY

Supply & erect wall and floor framing as shown. All timber framing to be termite resistant treated.

| Carpentry    |        |                        |               |             |  |  |
|--------------|--------|------------------------|---------------|-------------|--|--|
| ITEM         | Stress | Stress TIMBER NAME     |               | SPACING     |  |  |
|              | Grade  |                        |               |             |  |  |
| Bottom Plate | MGP10  | Radiata pine           | 90 x 45       |             |  |  |
| Top Plate    | MGP10  | Radiata pine           | 2 off 90 x 45 |             |  |  |
| Studs        | MGP10  | Radiata pine           | 90 x 45       | 450 centres |  |  |
| Noggings     | MGP10  | Radiata pine           | 90 x 45       |             |  |  |
| Floor joists |        | Refer Struct Eng comps |               |             |  |  |
| Floor sheet  |        | T&G Particleboard      | 19mm min      |             |  |  |

#### 7. THERMAL INSULATION

Provide thermal insulation as below.

| Item                      | Description | R-Rating | Manufacturer |
|---------------------------|-------------|----------|--------------|
| Wall insulation           | AirCell     | R 2.0    | Kingspan     |
| Roof insulation & sarking | AirCell     | R 2.0    | Kingspan     |

# 8. METAL ROOFING, CLADDING & PLUMBING

Metal roofing, downpipes, gutters.

| Item Description      |                  | Finish / Colour           | Supplier | Dimensions   |
|-----------------------|------------------|---------------------------|----------|--------------|
| Metal Roof corrugated | CustomOrb        | 'Evening Haze' Colorbond  | Lysaght  | 0.47mm gauge |
| Safety mesh           | Below roof sheet | Galvanised                | AusMesh  | 300x150x2    |
| Roof ventilators      | Whirlybird 2 off | 'Evening Haze' Powdercoat |          | 300 diam     |
| Eaves Gutters         | Quad 115         | 'Woodland Grey' Colorbond | Lysaght  | 90 x 115     |
| Downpipes             | Circular         | 'Gully' Colorbond         |          |              |
| Metal Wall Cladding   | Longspan         | 'Gully' Colorbond         | Stramit  | 0.42mm gauge |

#### 9. DOORS & DOOR FRAMES

Install external doors, door frames, as per schedule following.

Timber doors, paint finish

Deadlocks & Keylocks: Lockwood, key to match existing locks. Lever handle: Lockwood 1370 series brass '**Tempo' 71**, round rose

| Door<br>No | Location          | Description                 | Height x<br>width | Finish       | Door Hardware                   | Screen<br>Seal |
|------------|-------------------|-----------------------------|-------------------|--------------|---------------------------------|----------------|
| D10        | Extension         | External swing, solid core  | 2040 x 920        | Enamel paint | Deadlock, free<br>release lever | Weatherseal    |
| D11        | Extension         | Internal, swing, solid core | 2040 x 920        | Enamel paint | Lever, passage latch            |                |
| D12        | Tool Store        | Internal, swing, solid core | 2040 x 920        | Enamel paint | Lever, passage latch            |                |
| D13        | Material<br>Store | Internal, swing, solid core | 2040 x 920        | Enamel paint | Lever, passage latch            |                |
| D14        | Office            | Internal, swing, solid core | 2040 x 920        | Enamel paint | Lever, passage latch            |                |

# 10. WINDOWS, WINDOW FRAMES & GLAZING

Single glazed windows, safety glass minimum 4mm toughened Powdercoated aluminium frame, Bradnams by Wunderbar.

| Number | Location  | Description | Height | Width | Head | Hardware |
|--------|-----------|-------------|--------|-------|------|----------|
| W10    | Extension | Sliding     | 1000   | 1500  | 2100 | Key lock |
| W11    | Extension | Sliding     | 1000   | 1500  | 2100 | Key lock |
| W12    | Extension | Sliding     | 1000   | 1500  | 2100 | Key lock |

# 11. ROLLER SHUTTER DOORS

Supply & install powdercoated metal roller shutter doors, B&D or similar approved.

| Number | Location  | Height | Width | Head | Hardware |
|--------|-----------|--------|-------|------|----------|
| RD3    | Extension | 2400   | 2400  | 2400 | Key lock |
| RD4    | Extension | 2400   | 1800  | 2400 | Key lock |

# 12. ELECTRICAL DISTRIBUTION

Supply and installation of electrical transmission and reticulation materials from mains supply to required electrical power and light outlets. Locations to be confirmed. Quantities allowed for pricing only.

# ELECTRICAL FITTINGS SCHEDULE

| EEECTRICIE TITTI (OF SCHEDUE |                         |              |                              |         |  |  |  |  |  |
|------------------------------|-------------------------|--------------|------------------------------|---------|--|--|--|--|--|
| ITEM                         | LOCATION                | MAKE &       | DESCRIPTION                  | FINISH, |  |  |  |  |  |
|                              |                         | MODEL        |                              | COLOUR  |  |  |  |  |  |
| INTERNAL LIGH                | INTERNAL LIGHT FITTINGS |              |                              |         |  |  |  |  |  |
| Ceiling mounted              |                         |              | LED fitting, 9 off, TBS      |         |  |  |  |  |  |
| EXTERNAL LIG                 | EXTERNAL LIGHT FITTINGS |              |                              |         |  |  |  |  |  |
| Floodlight                   |                         |              | LED fitting, 2 off, TBS      |         |  |  |  |  |  |
| SWITCHING & ACCESSORIES      |                         |              |                              |         |  |  |  |  |  |
| Switches                     |                         | Clipsal 2000 | 2000 series, 4 off, @1000FFL | white   |  |  |  |  |  |
| Internal GPOs                |                         | Clipsal 2025 | 2000 Series, 8 off @ 300 FFL | White   |  |  |  |  |  |

# 13. FIRE EXTINGUISHERS

Provide fire extinguishers to comply with AS2444.